

BILLS OF QUANTITY OF CONSTRUCTION ACTIVITIES OF URWEGO BANK GICUMBI CREDIT OFFICE )					
S/N	Items & Description	Unit	Quantity	Rate	Amount (TVA Inclusive)
I	STAFF OFFICES AT FIRST FLOOR				
	<ul style="list-style-type: none"> <li>➤ Construction of 2 Strong Wall up to the Slab with Bloc Ciment (finishing <i>in</i> and <i>out</i> plus painting with Urwego bank colors weithaguard ) :</li> <li>1) One have the specification of meter of length (L=10.5 to H=3.2 m )</li> <li>2) Second have the specification of meter of length (L=6.8 to H=3.2 m )</li> </ul>	Item			
	<ul style="list-style-type: none"> <li>➤ Construction of an office of 12mm Gypsum board crewed into wooden framework : length (L= 3 to H=2.4m ) with a wooden door</li> </ul>	Item			
	<ul style="list-style-type: none"> <li>➤ Construction of an office of 12mm Gypsum board crewed into wooden framework : length (L= 3 to H=2) with a wooden door</li> </ul>	Item			
	<ul style="list-style-type: none"> <li>➤ Construction of two open cubical offices (for CAD and STL) of 12mm Gypsum board crewed into wooden framework : length (L= 5.5 to H= 1.8 m ) without door</li> </ul>	Item			
	<ul style="list-style-type: none"> <li>➤ Construction of archive room of 12mm Gypsum board crewed into wooden framework : length (L= 4.8 to H=) with a wooden door</li> </ul>				
	<ul style="list-style-type: none"> <li>➤ Protecting all glasses doors (L=10.5 to H=3.2 m ) 2 sides (where strong walls not applied) with 40x40 metallic tubes outside)</li> </ul>				
	<ul style="list-style-type: none"> <li>➤ Painting with Urwego Bank color as per the Bank logo and all necessary finishing with Cement ,sand mortar plaster to new masonry walls plus cleaning 100%</li> </ul>	Item			
	SUB TOTAL				
II	REHABILITATION OF OLD KICUKIRO BRANCH				
	Carefully demolish strong walls (inside of two rooms in the existing GICUMBI credit office building, and demolish Gypsum partitioning Triplex partitioning and repair of walls after remove all cabling and electrical installation until landlord approves and signes the handover report.	Item			
	Re-painting the building (out side and in side )	Item			
	Handover the field well cleaned and be responsible to remove all dust 100%	Item			
	SUB TOTAL				

Gd Total VAT Inclusive	:
---------------------------	---